Abstract of the quantities for constructing High School Building at Davangere :—

No.	Items of work	Units	Quantity
1	Earthwork excavation and filling in basement	C. yds.	842
2	Concrete in jelly and chunam	C. ft.	4,384
3	Stone in chunam foundation and basement	Do	18,520
4	Burnt brick in chunam superstructure	Do	25,367
5	Burnt stone slabs 6" thick roughly dressed	S. ft.	3,162
6	Brockets (stone) to projection of window cills, ...	Each	90
7	Bearing slabs below trusses	C. od	41
8	Cut stone pillars with base and capitals (7'x 9"x 9")	Each	37
9	Teakwood doors pannelled with hooks, hinge bittings, fastenings, etc., complete ..	S. ft.	473
10	Teakwood doors half pannelled, half venitioned with hooks, hinges, fittings, fastenings, etc., complete.	Do	221
11	Teakwood windows in front with iron bars venitioned shutters, hooks, hinges, fittings, etc.,	Do	360
12	Teak wood windows with half pannelled and half venitioned shutters, hooks, hinges, fittings, fastenings, and etc, complete.	Do	720
13	Teakwood ventilators with iron bars and glazed shutters	Do	283
14	Teakwood wall shelves with pannelled shutters and planks	Do	360
15	Teakwood king post trusses with iron fittings elolts and nuts, etc, complete ..	Each No.	20
16	Teakwood work verough and put up including wood oiling	C. ft	884·72
17	L. or T iron tursses 25 feet span with fishplates, colts, nuts, etc., complete ..	Each No.	2
18	Roofing with 1st class mangalore tiles on leakrupers including fishing etc., complete.	Sqr.	128·96
19	Ornamental ridge tiles set in mortar	R. ft.	406
20	Teak wood ornamental eave boards 6"x1" including painting	Do	295
21	Teak wood large boards including finials and pendents	Each No.	4
22	Flooring with 2" cuddappah slabes over 3" concrete and cement pointing ..	Sqr.	80·61
23	Chunam Plastering	Do	334·52
24	White and colour washing	Do	334·52
25	Painting with cement	Do	14·92
26	Silicate painting	Do	44 90
27	Cornice 24"x18" including plastering	R. ft.	377
28	Cornice 12"x9" including plastering	Do	664
29	String course below fringe work	Do	1,437
30	Cornice 6"x 6" for small pondiments over doors and windows	Do	495
31	Fringe work below cornice	Do	529
32	Pannelling over doors at passage	Each	2
33	Moulding 9"x 6" at sides and over doors and windows including plastering ..	R. ft.	1,377
34	Shafts to pillaste s bottom and top	Each	32
35	Binding wall at gable ends	R. ft.	224
36	Coping with burnt brick in chunam including plastering	Do	92
37	Teakwood gate with iron works fittings, fastenings etc., complete	Each	1
38	Zinc sheets for valleys with planking at sides	S. ft.	492
39	Teak wood screen, with frames, fittings, etc.,complete	Do	160
40	Clearing site and levelling ground Lumpsum Rs	Rs.	250
41	Inscription front gable L. S.	Do	20
42	Unforeseen charges	Do	500
43	Concrete drain airound inside with 1" wide cuddappah slabes at edges ..	R. ft.	273
44	Constructing latrin L. S.	Rs.	1,000

R. L. STEBLE,
Executive Engineer.

VICTORIA HOSPITAL, BANGALORE.

Notice.

Attention of the public is drawn to the tender notice published in the *Mysore Gazette* dated 13th September 1923, pages 597, 598—599, for the supply of diet articles, etc., for, the Victoria Hospital, Bangalore, during the calendar year 1924.

Correction to the notice calling for tenders for articles required for the Victoria Hospital, Bangalore, published in pages 597 and 599, Part VI, *Mysore Gazette*, dated 13th September 1923.

Article.	Quantity as published.	Quantity as corrected.
Straw	1,700 lbs.	17,000 lbs.

S. SUBBA RAO,
Medical Officer, in charge.